TIE-IN NEW 4" HP STL
TO EXISTING 2" HP STL
GAS MAIN
MAOP = 200 PSIG
NOP = 180 PSIG

REPLACE APPROX. 8,200' x 2" HP STL
WITH 4" HP STL GAS MAIN
MAOP = 200 PSIG
NOP = 180 PSIG

TIE-IN NEW 4" HP STL
TO EXISTING 2" HP STL
GAS MAIN
MAOP = 200 PSIG
NOP = 180 PSIG

PROPOSED 2" ABOVE GROUND
REGULATOR STATION
MIN. INLET = 90 PSIG
SET POINT = 55 PSIG
DESIGN FLOW = 80 MCFH

PROPOSED APPROX. 1,000' x 4" HP
STL GAS MAIN
MAOP = 200 PSIG
NOP = 180 PSIG

TIE-IN NEW 4" HP STL
TO EXISTING 4" HP STL
GAS MAIN
MAOP = 200 PSIG
NOP = 180 PSIG

PROPOSED APPROX. 6,700' x 4" MHP
PLS GAS MAIN
MAOP =60 PSIG
NOP = 55 PSIG

PROPOSED APPROX.
1,500' x 2" MHP PLS
GAS SERVICE TO SERVE
5 BUILDINGS

SITE

Effingham
CENSUS TRACT 303.05

SAVANNAH

Legend
County
Census_Tract

Atlanta Gas Light

EFFINGHAM COUNTY ECON-1

RINCON, EFFINGHAM COUNTY, GA
SAVANNAH SERVICE CENTER - 4970

N W E S

Revision Number	Revision Date	Sheet Number: 1 of 1	
		Drawn By:	
		Checked By:	
		Date:	