MFR-7 Project Technical Analysis - Gilmer

Project Information						Proposed Load	Proposed Main Section 1					Proposed Main Section 2					Proposed Service 1				Cost Estimate		Approvals			
Project Name	Address	Location Code	Project Summary	Requested By	Date Requested	Load (MCFH)	Category	Size	Type	Wall Thickness	Length (ft)	Category	Size	Type	Wall Thickness	Length (ft)	Size	Type	Wall Thickness	Length (ft)	Grand Total	Accuracy	Mgr	Director	VP	EVP
25CONV-COMM-3740-1329 Old Clear Creek Rd Ellijay GA 30536	1329 Old Clear Creek Rd, Ellijay, GA 30536	3740	Install approx. 1665' of 6" MHP PLS Main, 3500' of 4" MHP PLS Main, and 560' of 2" MHP PLS SVC	Dustin Lyle	11/25/2025	5.22		6"	PLS		1,665		4"	PLS		3,500	2"	PLS		560	$500,000	+50%/-30%				

Note: Steel MAOP 300 psi, plastic MAOP 60 psi unless otherwise noted.

Disclaimer

The attached estimate is for planning purposes only and cannot be used as a firm quotation from Atlanta Gas Light or our contractors. We will not be able to provide a firm quote until the project undergoes additional engineering and cost information is solicited from our vendors thru our formal bid process. The costs provided are based on rule of thumb estimates, local knowledge, and/or past history as well as mapping technologies. Keep in mind the estimated installation period can be delayed due to permitting delays and undetected terrain features (boring through rock formations, water crossings, etc.).

Project Information						Proposed Load	Proposed Main Section 1					Proposed Service 1				Cost Estimate		Approvals			
Project Name	Address	Location Code	Project Summary	Requested By	Date Requested	Load (MCFH)	Category	Size	Type	Wall Thickness	Length (ft)	Size	Type	Wall Thickness	Length (ft)	Grand Total	Accuracy	Mgr	Director	VP	EVP
25COMM-1780-49 CROOK RD Senoia GA 30276	49 CROOK RD SENOIA GA 30276	1780	Install Main & Service for Fire Station	Justin Hancock	1/13/2026	3.081		4"	PLS		2,300	1-1/4"	PLS		450	$380,000	+50%/-30%				

Note: Steel MAOP 300 psi, plastic MAOP 60 psi unless otherwise noted.

Disclaimer

The attached estimate is for planning purposes only and cannot be used as a firm quotation from Atlanta Gas Light or our contractors. We will not be able to provide a firm quote until the project undergoes additional engineering and cost information is solicited from our vendors thru our formal bid process. The costs provided are based on rule of thumb estimates, local knowledge, and/or past history as well as mapping technologies. Keep in mind the estimated installation period can be delayed due to permitting delays and undetected terrain features (boring through rock formations, water crossings, etc.).